## **Required Inspections – Commercial**

## **Footing Inspection**

This is done after footing has been formed and all steel is installed.

#### **Foundation Inspection**

This is done after foundation walls are formed and all steel is in place.

### **Rough-In Underground Plumbing**

This is done after the under slab plumbing has been installed. (Water 60 PSI) (DWV 5 PSI or 10 Foot Head)

# **Gas Piping Rough-In (contact Gibson County Utilities for gas inspections)**

This is done after all piping and fittings have been installed, prior to concealment. A pressure test is required at this time.

### **Framing Inspection**

This is done after the rough framing is in place and before any insulation or concealment of framing structure.

## **Above Ceiling**

At this time all fire separations must be complete and any sprinkler piping complete.

## **Sprinkler Hydro Test**

This is done at after all sprinkler piping has been installed.

# **Final Inspection**

This is done after the structure has been completed and prior to the issuance of Certificate of Occupancy.

Please notify Building Dept. at least 24 hours prior to any inspection.

Contact Milan Public Utilities for all electrical permitting and inspections.