

## **Required Inspections- Residential**

### **☐ Footing Inspection**

This is done after footing has been dug and reinforcing steel has been tied in place and grade stakes are installed.

### **☐ Rough-In Underground Plumbing**

This is done after under slab plumbing is installed but prior to it being covered.

### **☐ Gas Piping Rough-In**

This is done after gas piping has been installed and before concealment. (contact Gibson County Utilities for gas inspections)

### **☐ Framing Inspection**

This is done after the walls, floors, and the roof are in place. Framing inspections are done before any insulation has been installed. All rough in wiring and plumbing must be complete prior to framing inspection.

### **☐ Rough Plumbing Inspection (conducted during framing inspection)**

This is done after the Water and DWV piping has been installed and prior to concealment. All piping must be pressure tested at this time. **(60 PSI. for Water) (5 PSI. for DWV or 10 Foot Head)**

### **☐ Final Inspection**

This is done after all work has been completed and the structure is ready to be occupied. After all inspections have passed, the structure can be issued **Certificate Of Occupancy.**

Please contact Building Dept. at least 24 hours prior to required inspections.

Contact Milan Public Utilities for all electrical permitting and inspections.